

7 TIPS FOR SURVIVING A DATA CENTER HARDWARE MIGRATION

CHECKLIST BY

SUMMIT

Before you embark on a data center hardware migration, prepare yourself for the inevitable chaos that ensues when technology meets Murphy's Law. Here are seven tips for the journey.



PAD YOUR MOVE TIME LIKE A PLUSH MATTRESS.

Give yourself more time than you think you need at every step of the migration. No matter how good your team is, the truck will have a mechanical problem, a tech will come down with whooping cough, and dissimilar metals will cause a chemical reaction that welded screws in place. Expect delays — they're as likely as a forced computer update before a meeting.



USE PHYSICAL PORT NAMES IN YOUR CABLING MAPS.

Sometimes we get cabling maps that have instructions to connect a virtual bonded interface on a switch to “eth0” on a server. When making a cabling map, it’s best to use the manufacturer-given names as labeled on a device. Providing a hostname of a device can be helpful, but only if the hostname is also labeled on the device. It’s much faster when the names are physical (not logical) ports.



LABEL EVERY DEVICE WITH A UNIQUE IDENTIFIER.

Some servers have neat LCD screens that display the device's name. When it's migration time, though, that screen is off. If that screen is the only way to tell your servers apart, you need to break out the label maker and slap labels on the front and back of each device.



4 COLD-TEST.

Your servers, storage appliances, routers, firewalls, switches, etc. may all be running fine at the moment. However, if you were to shut them off, let them cool down, and power them back up, would they come back online? Make sure to check that every device recovers from a power-down. Failing hard drives, unsaved configurations, and bad connections on the circuit board tend to rear their ugly heads mid-migration.



AUDIT YOUR CABINET.

A thorough audit allows you to create an accurate inventory of your current cabinets, servers, switches, and cabling infrastructure. It also provides insights into the available space, power, and cooling capacity within each cabinet. This information helps you assess whether the new data center can accommodate your existing infrastructure or if additional resources are required. It ensures that you have adequate capacity to support your equipment and prevents overloading or underutilization of resources.

LABEL	DEVICE SOURCE RACK MOVE WINDOW LABEL CHECK	DEVICE SOURCE U	DEVICE DESTINATION RACK UNRACKED CRATE #	DEVICE DESTINATION U	RE-RACKED	DEVICE SIZE	MANUFACTURER	MODEL/DESC	S-15P/C14/C20 # POWER	CAT6 # C14	TWINAX/SAS # FIBER	HS DRIVES # SAS	INTERFACE	DESTINATION		
TQA101AS01	<input type="checkbox"/>	101	U26	<input type="checkbox"/>	<input type="checkbox"/>	1U	Cisco	2248TP	2	C14	35	2	0	0	LEFT <input type="checkbox"/>	chi2-switchdist-ed111a/02
TQA0B01-1 (TQA0B01)	<input type="checkbox"/>	101	U22	<input type="checkbox"/>	<input type="checkbox"/>	1U	Cisco	C-3750X	2	C14	35	0	0	0	LEFT <input type="checkbox"/>	chi2-switchdist-ed110a/03
TQA0B02-1(TQA0B03)	<input type="checkbox"/>	101	U19	<input type="checkbox"/>	<input type="checkbox"/>	1U	Cisco	C-3750X	2	C14	17	0	0	0	LEFT <input type="checkbox"/>	chi2-switchdist-ed111b/05
TQATS01	<input type="checkbox"/>	101	U14	<input type="checkbox"/>	<input type="checkbox"/>	1U	Avocent	ACS8000	2	C14	37	0	0	0	LEFT <input type="checkbox"/>	chi2-switchdist-ed111b/06
TQAPAF01	<input type="checkbox"/>	102	U33-34	<input type="checkbox"/>	<input type="checkbox"/>	2U	Palo Alto	PA-5020	2	C14	11	0	0	0	LEFT <input type="checkbox"/>	chi2-switchdist-ed111a/01
TQAPACF01	<input type="checkbox"/>	102	U30-32	<input type="checkbox"/>	<input type="checkbox"/>	3U	Palo Alto	PA-5250	2	C14	6	4	0	4	LEFT <input type="checkbox"/>	chi2-switchdist-ed111b/01
TQAVR03	<input type="checkbox"/>	102	U29	<input type="checkbox"/>	<input type="checkbox"/>	1U	Cisco	4431	2	C14	6	0	0	0	LEFT <input type="checkbox"/>	chi2-switchdist-ed111b/02
TQAIR01	<input type="checkbox"/>	103	U44-45	<input type="checkbox"/>	<input type="checkbox"/>	2U	Cisco	ASR1002	2	C14	4	1	0	0	LEFT <input type="checkbox"/>	chi2-switchdist-ed111a/05
TQAIS01	<input type="checkbox"/>	103	U39	<input type="checkbox"/>	<input type="checkbox"/>	1U	Cisco	C-3750X	2	C14	9	0	0	0	LEFT <input type="checkbox"/>	chi2-switchdist-ed111a/05
TQALB01	<input type="checkbox"/>	103	U33-36	<input type="checkbox"/>	<input type="checkbox"/>	4U	F5	VIPRION-C2400	2	C20	3	4	0	0		
TQACS01	<input type="checkbox"/>	103	U01-21	<input type="checkbox"/>	<input type="checkbox"/>	21U	Cisco	NEXUS 7000	6	C20	16	48	0	0		
TQA104AS01	<input type="checkbox"/>	104	U25	<input type="checkbox"/>	<input type="checkbox"/>	1U	Cisco	2232 PP	2	C14	0	26	0	0		
TQAMDS01	<input type="checkbox"/>	105	U01-14	<input type="checkbox"/>	<input type="checkbox"/>	3U	Cisco	9148F	2	C14	4	59	0	0		
TQA201AS01	<input type="checkbox"/>	201	U26	<input type="checkbox"/>	<input type="checkbox"/>	1U	Cisco	2248TP	2	C14	34	2	0	0		
TQA0B01-2(TQA0B02)	<input type="checkbox"/>	201	U22	<input type="checkbox"/>	<input type="checkbox"/>	1U	Cisco	C-3750X	2	C14	20	0	0	0		
TQA0B02-2(TQA0B04)	<input type="checkbox"/>	201	U19	<input type="checkbox"/>	<input type="checkbox"/>	1U	Cisco	C-3750X	2	C14	20	0	0	0		
TQATS02	<input type="checkbox"/>	201	U14	<input type="checkbox"/>	<input type="checkbox"/>	1U	Avocent	ACS8000	2	C14	34	0	0	0		
TQAPAF02	<input type="checkbox"/>	202	U33-34	<input type="checkbox"/>	<input type="checkbox"/>	2U	Palo Alto	PA-5020	2	C14	11	0	0	0		
TQAPACF02	<input type="checkbox"/>	202	U30-32	<input type="checkbox"/>	<input type="checkbox"/>	3U	Palo Alto	PA-5250	2	C14	6	4	0	4		
TQAVC02	<input type="checkbox"/>	202	U28	<input type="checkbox"/>	<input type="checkbox"/>	1U	Cisco	ASA5525	1	C14	6	0	0	0		
TQAVR04	<input type="checkbox"/>	202	U27	<input type="checkbox"/>	<input type="checkbox"/>	1U	Cisco	4431	2	C14	5	0	0	0		
TQAIR02	<input type="checkbox"/>	203	U44-45	<input type="checkbox"/>	<input type="checkbox"/>	2U	Cisco	ASR1002	2	C14	4	1	0	0		
TQAIS02	<input type="checkbox"/>	203	U39	<input type="checkbox"/>	<input type="checkbox"/>	1U	Cisco	C-3750X	2	C20	7	0	0	0		
TQALB02	<input type="checkbox"/>	203	U33-36	<input type="checkbox"/>	<input type="checkbox"/>	4U	F5	VIPRION-C2400	2	C20	3	4	0	0		
TQACS02	<input type="checkbox"/>	203	U01-21	<input type="checkbox"/>	<input type="checkbox"/>	21U	Cisco	NEXUS 7000	6	C14	14	47	0	0		
TQA204AS01	<input type="checkbox"/>	204	U25	<input type="checkbox"/>	<input type="checkbox"/>	1U	Cisco	2232 PP	2	C20	2	26	0	0		
TQAMDS02	<input type="checkbox"/>	205	U01-14	<input type="checkbox"/>	<input type="checkbox"/>	3U	Cisco	9841F	2	C14	4	56	0	0		
CJPQMS15	<input type="checkbox"/>	301	U09-12	<input type="checkbox"/>	<input type="checkbox"/>	4U	IBM	Power 740	2	C14	5	4	0	6		
CJDVMS01	<input type="checkbox"/>	303	U17-20	<input type="checkbox"/>	<input type="checkbox"/>	4U	IBM	Power P5-55A	2	C14	5	2	0	8		
CJDVMS09	<input type="checkbox"/>	303	U13-16	<input type="checkbox"/>	<input type="checkbox"/>	4U	IBM	Power 750	2	C14	5	4	0	4		
CJDVMS10	<input type="checkbox"/>	304	U09-12	<input type="checkbox"/>	<input type="checkbox"/>	4U	IBM	Power 750	2	C14	5	4	0	4		
CJ3DRL001	<input type="checkbox"/>	305	U13	<input type="checkbox"/>	<input type="checkbox"/>	1U	IBM	X3550-M3	2	C14	3	0	0	2		



FACTOR IN TIME TO TROUBLESHOOT.

After the migration, it takes time to get everything booted back up and running. Plan for some devices to not work — and give yourself plenty of time to figure out why.



REMEMBER, YOU'RE NOT A ROBOT.

When handling a colossal amount of equipment, take a page from the human playbook and adopt a shift-based approach to staffing. No one can work effectively after a 24-hour marathon. Embrace the power of rest.



There you have it — seven practical tips to survive your predictably unpredictable data center migration. Pad your move time, use physical port names, label like a champion, cold-test all the things, audit your cabinet, prepare to troubleshoot, and keep your humanity intact.

WHEN THE STAKES ARE HIGH, CALL SUMMIT.

Your IT team is not expected to carry out dozens of data center migrations each year, and rightly so. But Summit's migration specialists have performed hundreds of migrations over the years. We meticulously plan every step of the process, including measuring the width of doorways, hallways, and elevator openings in advance. When the unexpected comes up (and it will), we'll handle it without skipping a beat.

If you run into trouble, you can always count on the experienced data center operations team at Summit to migrate your IT gear for you. Learn about our data center migration service [here](#).